BID SUMMARY

PROJECT GMIA - Security & Wildlife Deterrent Perimeter Fencing - 2012

PROJECT NO.	**BIDS DUE**
A125-2001	Wednesday, April 18, 2012 @ 2:00 p.m.

CONTRACT #:	**BASE BID**
RITEWAY	$363,480.00
CENTURY FENCE COMPANY	$180,638.28
NORTHWAY FENCE	$162,868.60
DAKOTA INTERTEK CORP	
FENCE CONNECTION INC	$194,613.40

DBE	25 %
ADDENDUMS	1

BASE BID DESCRIPTION:

Base Bid work of the project will consist of the removal and replacement of the existing GMIA airport perimeter security fencing along the GMIA property line located along Howell Avenue. Work will begin east of the Skyway Hangar and extend west and south along Howell Avenue for approximately 3,900 feet of existing fence line. The new airport perimeter security fencing will have fabric buried two feet underground for wildlife deterrence, stand 10' high above ground, and have barbed wire arms 2'-0" high. Miscellaneous work will include asphalt milling, trenching, and asphalt replacement in certain locations along the new fence line. Various size swing gates, man gates , and slide gates will also be new installations along the new perimeter fenceline.

The DBD Department concurs with the DBE participation for the above recommended Bid. Please refer to the approved Form DBD-014C attached to the bid recommendation.