

V025-13807

ADDENDUM NUMBER 1

Rawson Avenue Lift Station

Project Number: V025-13807

Date of Addendum: June 13, 2013

This Addendum to the Request of Proposal is issued to modify, explain or correct the original documents, dated June 2013, and is hereby made part of the Request for Proposal. Acknowledge receipt of this addendum in the Letter of Transmittal, as part of your proposal submission.

**MODIFICATIONS TO RFP**

III. Scope of Consultant Services, 2. Basic Services, Task 1:

- i. After section a) **add** subsection a.1),

“a.1) Inspect and assess the storm sewer force main discharge structure, including back flow preventers. Inspect and assess the approximate 450 feet of storm sewer after this structure and the outfall point to the ditch line adjacent to the rail road. Inspect and assess the ditch line, check for positive drainage away from site. Coordinate with the rail road as needed for site access, etc.

III. Scope of Consultant Services, 2. Basic Services, Task 1:

- i. After section e) **add** subsection e.1),

“e.1) . Develop and provide recommendations as to what elements of the force main, storm sewer and drainage ditch need to be repaired or replaced for positive drainage for the long-term (20-year) operation. Include options for interim operation of the lift station prior to and while construction is underway.

III. Scope of Consultant Services, 2. Basic Services, Task 2:

- i. After section a) **add** subsection a.1),

“a.1) Prepare detailed design plans and specifications for bidding and construction of repairs and upgrades to the force main, storm sewer and drainage ditch. Develop an engineer’s cost estimate for the design. Provide review of shop drawings and submittals as well as on-site construction observation.

General Note 1:

Note that on 12/11/12 Milwaukee County received quotes to replace the pumps at the lift station from RDM Municipal Supply & Service, Inc. 2650 East Ryan Road, Oak Creek, WI 53154 (general: 414-856-1300 – Mick D’Alessandro Cell 414-531-5993.).

The quote provided specified 2 – 12” KBS Model KRT KL300-400/506 x NG-s Pumps. The estimated duty point was 5200 GPM @ 40’ TDH.

The current pumps in place are the originals installed in the late 1960’s.

V025-13807

General Note 2:

Photos from a site visit on 6/13/13 are available for review on Milwaukee County's RFP Website:  
<http://county.milwaukee.gov/ConstructionBidsandR23075.htm>

General Note 3:

Review the site plan attached to this addendum for the general location of features mentioned in this addendum.

End of Addendum No. 1



# RAWSON AVE LIFT STATION SITE PLAN



### Notes

Enter Map Description

THIS MAP IS NOT TO BE USED FOR NAVIGATION © MCAMLIS

**DISCLAIMER:** This map is a user generated static output from the Milwaukee County Land Information Office Interactive Mapping Service website. The contents herein are for reference purposes only and may or may not be accurate, current or otherwise reliable. No liability is assumed for the data delineated herein either expressed or implied by Milwaukee County or its employees.



### Legend

- County Boundary
- Highways, to 8k
- Street Centerlines, 0k to 8k
- Railroad 8k
- Water 8k
- Rivers 8k
- Airport 8k
- Landmarks 8k
- County Parks 8k
- Municipal Subdivisions 25k
- Tax Parcels
- AERIAL PHOTO 2010 HIGH RES\_ACU\_PLUS

1:3,117

519 0 260 519 Feet