P167-10422

DEPARTMENT of ADMINISTRATIVE SERVICES
ARCHITECTURE, ENGINEERING AND ENVIRONMENTAL SERVICES DIVISION

ADMINISTRATIVE CONTRACT AWARD
(Authorization: County Ordinance 44.14(2), Award of Public Works Contracts, Amended November 6, 1997)

I. PROJECT DESCRIPTION

Project No.: **P167-10422**
Project Name: **VETERANS PARK SHELTER DEMOLITION**

Project Location: **1010 North Lincoln Memorial Drive**
Milwaukee, Wisconsin 53202

Description of Project:

Demolition of existing structure (Veterans Park Shelter); located at Veterans Park, 1010 North Lincoln Memorial Drive, Milwaukee WI 53202. Demolition includes complete removal and disposal of debris off-site of shelter's concrete foundation (footings, foundation walls, slab-on-grade, etc...), masonry toilet room enclosure, open-air shelter (wood laminate structure), rough-sawn wood timber roof structure, and asphalt shingle roofing. Cap or remove existing underground utilities as shown and per governing utility requirements. Note; various demolition materials shall be recycled as indicated in Section 01 74 19 – Construction Waste Management and Disposal to meet Milwaukee County's Green Initiative. Demolition work also includes removal of existing asphalt-paved sidewalks as shown.

Work shall include backfilling of areas excavated to remove structure and sidewalks. Backfill areas to within 6-inches of existing adjacent grades and compact sub-grade to density required. Fill the remaining 6-inch depth with topsoil material, compact, and grade topsoil to match existing grades ensuring positive drainage. Apply mulch materials over all new topsoil and install erosion control mat to hold mulch in-place.

II. BID OPENING **Wednesday; March 13, 2013 at 2:00 PM**

III. RESPONSIVE, RESPONSIBLE BIDS RECEIVED

Contract 1 – Demolition: **Five (5) bids received.**

IV. RECOMMENDED LOW BID, RESPONSIVE, RESPONSIBLE CONTRACTOR

Contract 1 – Demolition: **Cream City Wrecking**

Base Bid:		**$25,375.00**
	CONTRACT AMOUNT	**$25,375.00**

V. FISCAL NOTE