

ADDENDUM NUMBER 3

VILLA TERRACE ART MUSEUM
SECURITY SYSTEM

2220 North Terrace Avenue
Milwaukee, WI
Project Number O509-10437

AND

CHARLES ALLIS ART MUSEUM
SECURITY SYSTEM

1801 North Prospect Avenue
Milwaukee, WI
Project Number: O511-10438

Date of Addendum: July 14, 2011

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated May 31, 2011, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

SPECIFICATIONS

1. Section 09900 PAINTING, PART # - EXECUTION, **CLARIFICATION:** "The museum staff will assist the contractor with the determination of paint color and acceptable matching of existing colors."
2. Section 09950 PLASTER RESTORATION, 1.03 QUALITY ASSURANCE, B. **CHANGE** paragraph to read: "Applicator: Company specializing in commercial plastering and quality replacement architectural plasterwork with at least **three TEN** (10) years experience."
3. Section 16015 HISTORIC BUILDING PRESERVATION AND RESTORATION, 1.3 PREQUALIFICATION, **CLARIFICATION:** "**Bidders shall provide information regarding their company and all sub-contractors, this information shall be submitted with the bid.**"
4. Section 16015 HISTORIC BUILDING PRESERVATION AND RESTORATION, 1.3 PREQUALIFICATION, 3.1 PRESERVATION, A. **CHANGE** paragraph to read: "Several rooms in the museum contain fragile and irreplaceable wall coverings – specifically, wall coverings made out of silk and leather. When working in these spaces, extra care must be performed such that these coverings do not get damaged. **The museum staff will assist the contractor with removal and preservation of wall covering when penetrations are required through the wall covering. Coordinate with museum staff prior to any work involving the wall coverings.**"
5. Section 16800 INTEGRATED SECURITY SYSTEM, 2.31 CLOSED CIRCUIT TELEVISION, **CHANGE** to read: " A.3.1 MP Fixed Dome Cameras
 1. The camera assembly shall be a **Peeco ID30DN-1 as scheduled on the drawings**, 3.1MP Indoor Sarix Dome as-scheduled, NO EXCEPTIONS."
6. Section 16800 INTEGRATED SECURITY SYSTEM, 2.35 STORAGE UNITS, **CHANGE** to read: "**70TB 42TB USABLE RAID STORAGE UNITS (per Location)**
Manufacturer: Nexsan Sataboy or EMC Clarian
 1. Nexsan: **5 3** SataBoy 14TB Storage or EMC Clarian equal
 2. Sataboy: **5 3** Single Controller 2FC 2iscsi
 3. SataBoy: 12 Cache 2GB
 4. Controller: Dual Raid Engine per Controller

End of Addendum No. 3

00900-1