

T069-13428

ADDENDUM NUMBER 1

MILWAUKEE COUNTY TRANSIT SYSTEM
FLEET MAINTENANCE
UNDERGROUND STORAGE TANK REMOVAL/UPGRADE
Site #215, Bldg. #125
1525 West Vine Street
Milwaukee, WI

Project Number: T069-13428

Date of Addendum: August 21, 2013

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated July 22, 2013, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

SPECIFICATIONS

SECTION 13455 AST INSTALLATION and USED OIL AST UPGRADE

CHANGE Article 2.3.A. as follows:

"Product delivery piping from tanks to pump room shall be 2-inch schedule 40 black steel welded piping conforming to ASTM A53."

ADD Article 2.4.E as follows:

"ASTs shall be protected by 6-inch diameter, 42-inch tall, schedule 40, bolt down bollards painted highway yellow. Bollards and installation locations shall comply with SPS 310. 430".

DRAWINGS

SHEET C2.0 IMPROVEMENTS PLAN

DELETE Bollard Detail. Provide bolt down bollards per Section 13455 Article 2.4.E as indicated above on Addendum 1 Specification additions.

End of Addendum No. 1