ADDENDUM NUMBER 1

MILWAUKEE COUNTY
ZOOLOGICAL GARDENS
EXIT DRIVE ASPHALT REPAVING
Site #355
10001 West Blue Mound Road
Milwaukee, WI 53226

Project Number: Z036-09476

Date of Addendum: November 16, 2011

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated November 4, 2011, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

SPECIFICATIONS

Section 02740 - ASPHALTIC CONCRETE PAVING (REPLACEMENT)
REPLACE Article 2.01, Paragraph D with the following:

D. Bituminous concrete pavement shall conform to Sections 450, 455, 460, and 465 of the WDOT Standard Specification.
   1. Provide HMA Type E-1 plant-mixed asphaltic concrete mixture conforming to the approved mix design.
   2. Aggregates used in the bituminous concrete pavement courses shall be crushed stone conforming of the following gradation requirements of Section 460.2.7 of the WDOT Standard Specification:
      a. Lower Layer – WDOT Type E-1, nominal 19.00 mm, and asphaltic cement with a performance graded designation of PG 58-28.
      b. Upper Layer - WDOT Type E-1, nominal 12.50 mm , and asphaltic cement with a performance graded designation of PG 64-22.
   3. Asphaltic concrete mixes used for surface course and binder course may contain salvaged or reclaimed asphaltic material in accordance with Subsection 460.2.5 and 460.2.6 of the WDOT Standard Specification, except salvaged material shall be limited to 25% RAP for lower layer and up to 20 percent RAP for upper layer.

End of Addendum No. 1