

ADDENDUM NUMBER 1

CURRIE PARK  
ELECTRICAL SERVICE  
UPGRADE  
Site #683, Bldg. #2470  
3535 North Mayfair Road  
Wauwatosa, WI

Project Number: P332-15626

Notice Number: 7049

Date of Addendum: October 15, 2015

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated September 4, 2015, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

SPECIFICATIONS

1. Section 26 10 16 Utility Services. DELETE paragraph 3.02 A 3 "Any charges by the utility to provide service described herein in lieu of overhead service shall be borne by the EC and included in the Base Bid".

DRAWINGS

1. Drawing ES1.0 Electrical Site Plan. ADD General Note #4: "Contractor to contact Diggers Hotline prior to starting any excavation work. All underground utilities shall be marked by Diggers Hotline prior to digging."
2. Drawing ES1.0 Electrical Site Plan. ADD General Note #5: "All excavation shall be restored to original condition. The contractor shall backfill, tamp, replace topsoil, re-seed and provide seed cover, all as directed by the County."
3. Drawing ES1.0 Electrical Site Plan. ADD General Note #6: "The contractor shall contact Gene Andrzejak at Parks Maintenance ((414) 258-2322) for removal and/or modification of existing landscaping needed for installation of new electrical gear."
4. Drawing ES1.0 Electrical Site Plan. REVISE The first sentence of General Note #3 to read "The Electrical Contractor shall bore all underground piping to new pole locations."
5. Drawing ES1.0 Electrical Site Plan. REVISE The paragraph addressing the existing pole near the Pumphouse to read: "Approximate location of existing light pole. Under alternate bid, a WE Energies transformer pad is to be installed near this pole. Note that this pole is in a clear area about half way up the hill from the pumphouse. Excavate as needed to install a level pad on this steep slope. The contractor shall install secondary conduits as required by WE Energies to an exterior wall mounted meter on the pumphouse wall."

End of Addendum No. 1