ADDENDUM NUMBER 1

MILWAUKEE COUNTY
FIRE ALARM SYSTEM REPLACEMENTS
at

Vel Phillips Children's Court Center
10201 West Watertown Plank Road
Wauwatosa, WI 53226
Project Number: G017-14425

Research Park Technology Center
10437 Innovation Drive
Wauwatosa, WI 53226
Project Number: G018-14426

Child & Adolescent Treatment Center
9501 Watertown Plank Road
Wauwatosa, WI 53226
Project Number: G019-14427

Notice Number: 7017

Date of Addendum: June 3, 2015

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated April 15, 2015, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

BIDDING AND CONTRACT CONDITIONS

Document 00400 Bid Form
CHANGE page 00400-3, COMMENCEMENT AND COMPLETION OF CONTRACT WORK, as follows:
The undersigned agrees, if signatory to the Contract, to commence work upon receipt of Notice to Proceed and achieve Substantial Completion of the Work within, 120 calendar days for Contract 1, 30 calendar days for Contract 2, and 30 calendar days for Contract 3).

DRAWINGS

Sheets E001 through E901, CHANGE Fire Alarm Symbols on all sheets as shown on attached document A1 issued as part of this Addendum 1.

End of Addendum No. 1

FIRE ALARM SYMBOLS

CD #	FIRE ALARM HORN / STROBE, CEILING MOUNTED - NEW CD# INDICATES CANDELA RATING
CD # SO	FIRE ALARM STROBE ONLY, CEILING MOUNTED - NEW CD# INDICATES CANDELA RATING
	FIRE ALARM STROBE - WALL MOUNTED - EXISTING TO BE REMOVED UNLESS OTHERWISE NOTED
	FIRE ALARM HORN/STROBE - WALL MOUNTED - EXISTING TO BE REMOVED UNLESS OTHERWISE NOTED
	FIRE ALARM HORN - EXISTING TO BE REMOVED
	FIRE ALARM BELL - EXISTING TO BE REMOVED
	FIRE ALARM PULL STATION - EXISTING TO BE REPLACED AT 42" AFF UNLESS NOTED OTHERWISE
K	FIRE ALARM STATION - KEY ACTIVATED EXISTING KEY STATION TO BE RETROFIT WITH A NEW 'MIM' UNLESS NOTED OTHERWISE
S	FIRE ALARM SMOKE DETECTOR - EXISTING TO BE REPLACED UNLESS NOTED OTHERWISE
S M	FIRE ALARM SMOKE DETECTOR WITH GUARD COVER - EXISTING DEVICE TO BE REPLACED UNDER EXISTING GUARD COVER UNLESS NOTED OTHERWISE
SD	FIRE ALARM DUCT SMOKE DETECTOR - EXISTING TO BE REPLACED UNLESS NOTED OTHERWISE
T	FIRE ALARM THERMAL DETECTOR - EXISTING TO BE REPLACED UNLESS NOTED OTHERWISE
CIM	FIRE ALARM CONTROL INTERFACE MODULE - NEW
MIM	FIRE ALARM MONITOR INTERFACE MODULE - NEW
FA / CP	FIRE ALARM CONTROL PANEL - EXISTING TO BE REPLACED
FA / ANN	FIRE ALARM ANNUNCIATOR PANEL - EXISTING TO BE REPLACED
FA / RP	FIRE ALARM REMOTE PANEL - EXISTING TO BE REPLACED
FA / RP	FIRE ALARM REMOTE PANEL - NEW FOR UPGRADE OF SYSTEM AS REQUIRED

LPA # 8188

LEEDY & PETZOLD ASSOCIATES, LLC

ADDENDUM #1

DATE:
06/ 03/ 2015

FIRE ALARM SYSTEM REPLACEMENT / UPGRADE

A1