

ADDENDUM NUMBER 3

MILWAUKEE COUNTY CORRECTIONAL FACILITY
ACC NORTH DORMITORY HVAC RENOVATIONS
Site #295, Bldg. #595
8885 South 68th Street
Franklin, WI 53132

Project Number: J021-14416

Notice Number: 6917

Date of Addendum: May 22, 2014

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated April 11th, 2014, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

DRAWINGS

1. **REVISE** New Work Sheet Note 4 on Sheet E100A to read as follows: "Provide new Simplex duct smoke detector. Provide all control/interface wiring between detector, fire alarm control panel, and rooftop unit, and power wiring and conduit for the detector. There are a total of 13 duct smoke detectors located where new and existing return air ductwork enter each dormitory floor area (see mechanical drawings for locations). EC shall field coordinate with the MC for all duct smoke detectors shown on the mechanical drawings. The EC shall be responsible for the control module, control and power wiring, and all interface wiring between the duct smoke detector control module, air handling unit, and the fire alarm system for all 13 duct smoke detectors shown on the mechanical drawings."
2. **REVISE** New Work Sheet Note 6 on Sheet E100A to read as follows: "Existing duct smoke detector to be replaced with new Simplex duct smoke detector and relocated. Extend fire alarm circuitry."
3. **REVISE** New Work Sheet Note 4 on Sheet E101 to read as follows: "Provide new Simplex duct smoke detector. Provide all control/interface wiring between detector, fire alarm control panel, and rooftop unit, and power wiring and conduit for the detector. There are a total of 13 duct smoke detectors located where new and existing return air ductwork enter each dormitory floor area (see mechanical drawings for locations). EC shall field coordinate with the MC for all duct smoke detectors shown on the mechanical drawings. The EC shall be responsible for the control module, control and power wiring, and all interface wiring between the duct smoke detector control module, air handling unit, and the fire alarm system for all 13 duct smoke detectors shown on the mechanical drawings."

End of Addendum No. 3