ADDENDUM NUMBER 4

LINCOLN PARK
GOLF COURSE IRRIGATION
Site # 694
1000 West Hampton Avenue
Glendale, WI

Project Number: P221-13647

Notice Number: 6887

Date of Addendum: February 6, 2014

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated December 20, 2013, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

BIDDING DOCUMENTS

SPECIFICATIONS

Section 220600 – Pipe and Pipe Fittings

- Revised 2.1 Domestic Water: Water Distribution Piping Material: ASTM D2241 SDR 21

CONSTRUCTION DRAWINGS

Plans - Sheet P101

- Detail 5 – Existing Meter Pit Detail
  1. Remove existing 4" water meter and replace with a new 6" water meter. The new 6" water meter shall be furnished by Milwaukee Water Works. Contractor to coordinate meter replacement with Milwaukee Water Works.
  2. Replace valves upstream and downstream of meter, valve on meter bypass and valve to 3" test line.

End of Addendum No. 4