

M023-15421

ADDENDUM NUMBER 1

MILWAUKEE PUBLIC MUSEUM  
MECHANICAL UPGRADES  
(CONDENSATE DISCHARGE)  
Site #275, Bldg. #60  
800 West Wells Street  
Milwaukee, WI 53233

Project Number: M023-15421

Notice Number: 7089

Date of Addendum: March 4, 2016

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated December 21, 2015, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

BIDDING, CONTRACT DOCUMENTS AND DRAWINGS

1. Mechanical Clarification – The condensate return system shall remain operational during construction. Contractor shall maintain the operation of one submersible condensate pump during the installation of the new pumps. As an alternative, contractor may install a temporary submersible condensate pump.
2. Electrical Clarification – Submersible Condensate pumps: Contractor shall demolish existing wire and conduit from electrical panel to equipment. Conduit below slab shall be capped at floor. Contractor shall provide new wire and conduit from electrical panel to equipment.
3. Electrical Clarification – REF-1: Contactor shall provide new wire from electrical panel to REF-1 motor and VFD. Contractor may re-used conduit.

End of Addendum No. 1