

M019-15420

ADDENDUM NUMBER: Addendum - Two
PROJECT TITLE: Milwaukee Public Museum
NORTH PLAZA – Waterproofing Membrane Replacement
Site Number: 275 Building Number: 60
800 West Wells Street
Milwaukee, Wisconsin 53233-1478
Project Number: M019-15420

DATE OF ADDENDUM: March 23, 2016

This Addendum to the Contract Documents is issued to modify, explain or correct the original Documents, Dated JANUARY 28, 2016 and is hereby made part of the Contract Documents. Acknowledge receipt of this addendum in the space provided on the Bid Form, or bid maybe rejected.

SPECIFICATIONS

Core Sample Report

Clarification:

Two of the core samples do have Welded Wire Mesh. Existing documents are not definitively clear if the existing concrete is reinforced.

DRAWINGS

CONTRACT-A

Sheet A1.03

Revise Keyed Note 16 as follows:

Remove existing reinforced 4-inch concrete topping slab, filter fabric, 1/2-inch Mira drain board, and waterproofing membrane (1-layer of 0.080 EPDM) down to existing structural concrete deck.

CONTRACT-B

Sheet A1.08

Revised Detail 2 / A1.08 title as follows:

EXISTING EASTSIDE RAILING AND LIMESTONE PANEL

Sheet A1.08

Revised Detail 3 / A1.08 title as follows:

EXISTING EASTSIDE RAILING BASE

Sheet A1.09

Revised Keyed Note 2 as follows:

Remove existing reinforced 4-1/4 inch to 4-3/4 inch concrete topping slab, 1/2-inch thick built-up asphaltic membrane and 2-inches insulating concrete fill down to existing structural concrete deck.

Revised Keyed Note 5 as follows:

Remove existing concrete (reinforced) poured-in-place stairs & existing waterproofing membrane down to existing structural concrete deck.