

ADDENDUM NUMBER 2

CALVIN MOODY PARK COMMUNITY
BUILDING, SPLASH PAD, AND PARK RENOVATION
Site #701, Bldg. #1460
2200 West Burleigh Street
Milwaukee, WI 53206

Project Number: P191-11437

Date of Addendum: March 4, 2014

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated January 29, 2014, and is hereby made part of the Contract Documents.

MODIFICATIONS & CLARIFICATIONS TO BID FORM

1. Document 00410 – Bid Form:
 - a. Page 1, **DELETE** “Bids Due: March 5, 2014” and **REPLACE WITH** “Bids Due: March 12, 2014

MODIFICATIONS & CLARIFICATIONS TO TECHNICAL SPECIFICATIONS

1. Document 00010 – Table of Contents, Volume 2:
 - a. **CLARIFICATION** to index: Specification Section 26 29 00 Low-voltage Controllers: **REVISE** 26 29 00-2 **TO** 26 29 00-4
2. Document 00100 – Invitation to Bid:
 - a. Section .2 BID, **DELETE** entire paragraph 1 and **REPLACE WITH** the following:

“Sealed bids are due in the office of the County Clerk, Courthouse - Room 105, 901 North 9th Street, Milwaukee, WI 53233, no later than 2 P.M., Wednesday, March 12, 2014”
3. Document 00410 – Sample Bid Form:
 - a. Page 1, **DELETE** “Bids Due: March 5, 2014” and **REPLACE WITH** “Bids Due: March 12, 2014
4. Specification Section: 02805 “Vinyl Coated Chain Link Fencing”:
 - a. **CHANGE:** Specification Section 02805 refers to fence post and rail sizes incorrectly. The tables shown on the detail drawings shall trump.
5. Specification Section: 087100 “Door Hardware”:
 - a. **REVISE** Specification Section 087100-11, part 2.13, H, 1, with the following:

“1. 4 ½” Recessed Mounted Weather Proof Wired Wall Actuator Mount, unless noted otherwise.”

MODIFICATIONS & CLARIFICATIONS TO DRAWINGS

1. Sheets C801 & C802 – Splash Pad Details:
 - a. **CLARIFICATION:** The “Height & Leveling Control Anchor Studs with Hardware” are provided by the owner furnished aquatic play products (VORTEX).
2. Sheet A201 – New Work Plan - First Floor:
 - a. **REVISE** sheet A201 dated 2/11/14 as follows:
 - i. Provide on both sides of the door, automatic entrance actuators for door 101-1. Actuators are to be recessed in the wall on the jamb side of the door. Coordinate both locations with Electrical contractor.
 - ii. Provide on both sides of the door, automatic entrance actuators for door 101-2. One actuator is to be located in room 101, recessed in the wall between vestibule 101 and storage room 103 located 4'-0" north of the south wall of vestibule 101. The second is to be located in room 102 on the north wall on the jamb side of door 101-2 recessed in the wall. Coordinate both locations with the Electrical contractor.
3. Sheet E111 – New Work Plan - Power And Systems:
 - a. **REVISE** sheet E111 dated 1/27/14 as follows:
 - i. Revise location of new work keynotes “4” per revisions to architectural sheet A201 noted above.
4. Sheet 201 – Foundation Plan:
 - a. Drawing 4/S201, **DELETE** dimension label “VARIES BEAR ON ROCK” and **REPLACE WITH** “ 4'-0” MINIMUM”.
 - b. Drawing 1/S201, **CLARIFICATION:** Equipment pad shall be sized to accommodate equipment provided in specification section 23 62 13 “Package Air Cooled Refrigerant Compressor and Condensing Units”.

End of Addendum No. 2