

ADDENDUM NUMBER 1

CALVIN MOODY PARK COMMUNITY
BUILDING, SPLASH PAD, AND PARK RENOVATION RE-BID
Site #701, Bldg. #1460
2200 West Burleigh Street
Milwaukee, WI 53206

Project Number: P191-11437

Date of Addendum: July 31, 2014

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated July 9, 2014, and is hereby made part of the Contract Documents.

MODIFICATIONS & CLARIFICATIONS TO BID FORM

1. Document 00410 Bid Form & 00410 Bid Form Sample:
 - a. Page 00410-1, **DELETE** "Bids Due: August 13, 2014" and **REPLACE WITH** "Bids Due: **August 20, 2014**".
 - b. Page 00410-1, **REVISE** as follows,

*"hereby agree to execute contract and furnish a satisfactory surety bond in the amount specified to complete the above project in strict accordance with Contract Documents dated **July 9, 2014**"*

MODIFICATIONS & CLARIFICATIONS TO SPECIFICATIONS

2. Document 00100 – Invitation to Bid:
 - a. Page 00100-1,2. Bid: **REVISE** as follows,

*"Sealed bids are due in the office of the County Clerk, Courthouse - Room 105, 901 North 9th Street, Milwaukee, WI 53233, no later than 2 P.M., Wednesday, **August 20, 2014**"*
3. Document 00800 Supplementary Conditions:
 - a. Page 00800-7, 12.07 Liquidated Damages, A: **DELETE** "Two Hundred Fifty Dollar" and **REPLACE WITH** "Two Hundred Dollar" at all instances within paragraph.
4. Special Provisions:
 - a. Page SP 38, Alternate #3 – Helios System Installation:
 - i. **ADD:** Helios System Installation shall include the pickup and delivery of the owner supplied Helios fitness station from the Parks Department Maintenance Yard (1150 N 68th St, Wauwatosa, WI 53213). The Helios shipping dimensions are approximately 48" wide x 48" long x 87" high. The shipping weight of the Helios is approximately 588 pounds. The Helios is to be anchored to the concrete pad with four 6 ¼" long x ¾"

diameter zinc plated wedge anchors placed to a depth of 4 ½ per the manufacturer's instructions. The Contractor shall provide anchors.

- ii. **ADD:** Concrete Pad Pavement shall be 8" thick with 8" Compacted Aggregate Base per manufacturers recommendations in lieu of the Type 3 concrete referenced on Plan Sheet C330. This work remains incidental to this bid item

End of Addendum No. 1