

## BID SUMMARY

**PROJECT NAME:**

***Central Services Maintenance Garage Roof***

***Replacement***

**PROJECT NO.**

P251-12613

**BIDS DUE**

Wednesday, November 20, 2013

**CONTRACT #1:**

**BASE BID**

**DBE REC'D**

Walsdorf Roofing Company Inc.	<u>\$222,500.00</u>	<input checked="" type="checkbox"/>
Winding Roofing Company Inc.		<input type="checkbox"/>
Schranz Roofing & Sheet Metal	<u>\$199,200.00</u>	<input checked="" type="checkbox"/>
Langer Roofing & Sheet Metal	<u>\$172,950.00</u>	<input checked="" type="checkbox"/>
Kaschak Roofing		<input type="checkbox"/>
Royalty Roofing, LLC		<input type="checkbox"/>
Dekoven Enterprises		<input type="checkbox"/>
All American	<u>\$186,328.00</u>	<input checked="" type="checkbox"/>

**DBE** 25 %

**ADDENDUMS** Two (2)

**BASE BID DESCRIPTION:**

The Central Services Maintenance Garage roof replacement, ROOF NO. 5 – approximately 9,650 square feet, will be released for public bidding to remove the existing built-up roofing and replaced with a new roofing membrane. Demolition will include Removal of existing built-up roofing and insulation to expose the existing decking. The roofing contractor shall inspect existing wood roof decking for deterioration. New roofing system will include: Fully adhered 60-mil EPDM single ply roof membrane. Base insulation will be two layers of isocyanurate insulation (each layer 2 1/2 – inches), total depth of 5 – inches on a vapor retarder. Also provide roof saddles of tapered isocyanurate (1/4 – inch per foot) to direct storm water to roof drains. Roof drains: Existing roof drains shall be removed and replace with new. Flashings: Remove existing flashings and replace with new. Parapet copings: Existing to remain, roofing contractor shall inspect existing copings and replace damage copings as needed.

The DBD Department concurs with the DBE participation for the above recommended Bid. Please refer to the approved Form DBD-014C attached to the bid recommendation.