

O517-14626

ADDENDUM NUMBER 1

Milwaukee County  
War Memorial Center, Milwaukee Art Museum  
Concrete Deck Repairs  
750 N.Lincoln Memorial Drive, Milwaukee, WI. 53202

Date of Addendum: August 25, 2014

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated August 8, 2014, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

BID FORM

Bid Form page 00410-3.1

**Item # 4:** remove " 6 " And replace with " 7 ". Addition electrical outlet to be replaced at east edge of "Honor Roll" monument.

Bid Form page 00410-3.2

**Item # 9:** remove " 34 l.f." And replace with " 50 l.f.". Additional expansion joint replacement on north stairs to be included.

SPECIFICATIONS

**section 07140: HOT FLUID APPLIED WATERPROOFING:**

**P. 07140-8 SECTION 3.5 PARAGRAPH B:** Remove, "Flood testing requires 2" minimum head of water for a 24 hour period and must be approved by manufacturer." Replace with, "**Vector Mapping testing will be required for all approved systems.**"

DRAWINGS

**SHEET A1:**

Revise Note to General Notes: "4. Only lightweight lifts shall be used on deck. Maximum live loading to be 80 psf as distributed through area of equipment use."

**SHEET A2:**

Add Note to sheet: " Remove outlet at east edge of Honor Roll monument and place new outlet mounted to bottom of bird cage stair as directed by Engineer.

**SHEET A6:**

Details 14/A6 and 13/A6: Add notes, "**Expansion joint to be EMSEAL type SJS – 400 with 9-Inch sand blasted stainless steel plate. Contractor to notch concrete to provide 4-inch opening.**"

CLARIFICATIONS

1. Item 2 includes all demolition of concrete surfaces, insulation and waterproofing and accessories for all areas where demolition is called for. Item no. 3 is placing the decking systems on the horizontal surfaces and item 8 is placing the decking system on the south stair areas only.
2. Existing S.S. flashing is not required to be polished beyond standard site clean-up.

**End of Addendum No. 1**

00900-1