

ADDENDUM NUMBER 2

CHILDREN'S COURT AND COUNTY FLEET/SHERIFF BUILDINGS
INDEPENDENT HEATING SYSTEMS

Milwaukee County Grounds
West Watertown Plank Road
Wauwatosa, WI

Project Number: O143-12436

Date of Addendum: January 21, 2013

This Addendum to the Contract Documents is issued to modify, explain or correct the original documents, dated December 21, 2012, and is hereby made part of the Contract Documents. Acknowledge receipt of this Addendum in the space provided on the Bid Form, or bid may be rejected.

PROJECT DRAWINGS

1. Sheet T001 – Project Scope and General Notes:
Add: General note #7 to the project scope and general notes.
#7. For disposal of scrap metal, contractors may use existing scrap metal dumpster located at the facility.
2. Sheet T001 – Project Phasing and Schedule: Project schedule indicates Final Completion Date of August 15, 2013. Final Completion Date in section 3.5 of the project schedule shall be changed to October 15, 2013 to allow for final boiler acceptance testing to be completed under cooler weather conditions. Substantial Completion shall remain August 1, 2013 which shall include initial boiler start-up and operational testing.
3. Sheet A110 – Partial First Floor Demolition Plan:
Add: Demo note #6 to demo key notes.
#6. Completely remove existing exterior window system and louver from existing exterior masonry wall. Cut patch & return remaining masonry opening for new glass block infill.

Add: Demo note #6 to demo floor plan, Detail 1/A110. Locate at exterior window opening, between grid lines OH & OG.
4. Sheet A110 – Partial First Floor New Work Plan:
Add: New work note #12 to new work key notes.
#12. Infill existing (nominal) 6'H x 8'W masonry window opening in with 4" x 8" x 8" obscure glass block.

Add: new work note #12 to new work floor plan, detail 2/A110. Locate at exterior window opening, between grid lines OH & OG.
5. Sheet E110 – Fleet Management Partial First Floor Plan Electrical Demo Work:
Add: Demo work general note #2 to demo work general notes.
#2. Electrical Contractor shall maintain temporary lighting in Mechanical Room.
6. Sheet M130 – Fleet Management Partial First Floor Plan – Ducting and Venting: Delete the reference note pointing to louver located above the window which indicates, "Provide insulation and sheet metal to cap 48" x 24" louver inside." Widow is being removed and replaced with a glass block infill.

O143-12436

7. Sheet M220 – Children's Court Partial Basement Floor Plan – New Work: Gas meter being provided by WE Energies shall be located at the outside corner of the building along the north face of the building (approximately 5 feet plan south). Contractor shall provide the additional length of 4" natural gas piping along the outside of the building.

End of Addendum No. 2