

BID SUMMARY

PROJECT NAME:

MPM - Mechanical Room Floor Repair North Wing AHU Replacement

PROJECT NO.

M027-17417

BIDS DUE: August 22, 2018 at 2:00 P.M.

CONTRACT 2: Mechanical Room Floor Repair**BASE BID****TBE**

A. J. Heinen Construction, Inc.

☐

Wm. Sackerson Construction Co., Inc.

\$103,000.00

☒

DBE 10%
ADDENDUMS 2

BASE BID DESCRIPTION:

Sawcut existing exterior slab and install bulkhead as detailed. Fill void space below interior structural slab with self-consolidating concrete as specified and let cure for two (2) days. Removal of the existing deteriorated concrete topping. Scarify and/or shot blast the top surface of existing interior concrete structural slab to provide bondable surface. Install bonding agent on the top surface. Install concrete reinforcing as detailed for concrete equipment pads and concrete floor topping. Pour concrete topping and concrete equipment pads, cure to reduce shrinkage and cracking before installing AHU equipment (N.I.C.)

CBDP concurs with the DBE participation for the above recommended Bid. Please refer to the approved Form DBD-014C attached to the bid recommendation.