

**ADDENDUM NO. 1**

Wilson Park Senior Center Chiller Replacement Project  
2601 West Howard Avenue  
Milwaukee, Wisconsin 53221

April 17, 2019

This addendum modifies the project specifications and Drawings and is hereby incorporated as part of the project documents.

1. Drawing M-2: All chilled water piping exterior to the building shall have its insulation and metal jacket removed.  
This piping as well as the new piping shown on the drawing shall be insulated and covered with PVC weather tight jacket as specified. (Section 23 07 00 HVAC Insulation)
2. Antifreeze: It is estimated that 35 to 40 gallons of antifreeze polypropylene glycol will be needed for 35% solution with chilled water piping.
3. Electrical: Splicing of existing power cabling to new chiller is un-acceptable
4. Electrical: Power for relocated hot water pump P-4 shall be extended to pumps new location as shown on M-3.